

**Considerations need to be made for;**

- Transporting of components from delivery vehicle to installation location
- Due to the size and weight of components it is advised that a tail lift will may not be available so arrangements should be in place for unloading of vehicle
- Suitable fixings for PCS and battery racking
- Ventilation (Unless provided as part of a containerised solution)
- G99 relay, if required
- Installation of metering (Metering and split core CT clamps are included)
- Physical installation of battery racking, PCS, AC and meter cabling
- Connection and testing of AC supply
- Disposal of packaging